

[illegible]

S.No	DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6=(3X5)
1	DX- SPLIT TYPE AIRCONDITIONING UNITS: Supply, Installation, Testing & Commissioning of DX Split Air-conditioning wall mounted Decorative Type Units, complete refrigerant piping, foam insulation, cladding, refrigerant tray, cable tray, conduit, Thermostat, control cable, electric wiring & accessories. Indoor unit with all sections and components given in the schedule and specifications of DX Split Air-conditioning Units, including uplifting / lowering, loading / unloading at site, complete in all respect and as directed by the Engineer incharge in following sizes and capacities. GROUND FLOOR i DX- 01 to 06 / CU- 01 to 06 (2.0 TR Capacity) (SEMINAR / L.T -01) ii DX- 01 to 06 / CU- 01 to 06 (2.0 TR Capacity) (SEMINAR / L.T -02) FIRST FLOOR i DX- 01 to 06 / CU- 01 to 06 (2.0 TR Capacity) (SEMINAR / L.T -03) ii DX- 01 to 06 / CU- 01 to 06 (2.0 TR Capacity) (SEMINAR / L.T -04)				
		Nos.	6		
		Nos.	6		
		Nos.	6		
		Nos.	6		
AMOUNT CARRIED TO HVAC SUMMARY					

S.No	DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6=(3X5)
2	HVAC FANS Supply, installation, testing and commissioning of HVAC fans, as per equipment schedule, as shown on the drawings including all labour, material and accessories, complete in all respect and to the satisfaction of engineer incharge. GROUND FLOOR i EF - 01 TO 04 (200 cfm) Propeller Type Fan ii EF - 01 TO 04 (200 cfm) Propeller Type Fan FIRST FLOOR i EF - 01 TO 04 (200 cfm) Propeller Type Fan ii EF - 01 TO 04 (200 cfm) Propeller Type Fan				
		No.	4		
		No.	4		
		No.	4		
		No.	4		
AMOUNT CARRIED TO HVAC SUMMARY					

S.No	DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6=(3X5)
3	CONDENSATE PIPING Providing and fixing, uPVC Class 'E' pipes and fittings as per BS 3505 (EN 1401) for Condenser Water drain including foam insulation, as indicated on drawings, as per specifications and Engineers approval.				
i	1" dia	R.Ft.	240		
AMOUNT CARRIED TO HVAC SUMMARY					

S.No	DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6=(3X5)
4	CIVIL WORKS Making and cutting in walls, slabs and preparation of CC foundation for Condensing Units, Fans and all other HVAC equipments in all other work such as Openings, Penetrations, Firestopping, Wooden Frame Sleeves and Pipe Sleeves, plaster finish etc as directed by Engineer Incharge, complete in all respect.	Job	1		
AMOUNT CARRIED TO HVAC SUMMARY					

S.No	DESCRIPTION	UNIT	QTY.	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6=(3X5)
5	SHOP DRAWING & AS-BUILT DRAWING Providing Shop Drawings and As Built Drawings in A1 size with Electronic Copies, as specified in specifications, complete in all respect and as directed by the Engineer incharge.	Job	1		
AMOUNT CARRIED TO HVAC SUMMARY					